

FLORIDA DEPARTMENT OF
Business & Professional Regulation

[BCIS Home](#) | [Log In](#) | [User Registration](#) | [Hot Topics](#) | [Submit Surcharge](#) | [Stats & Facts](#) | [Publications](#) | [Contact Us](#) | [BC](#)



Product Approval
USER: Public User

[Product Approval Menu](#) > **Application Detail**

OFFICE OF THE
SECRETARY

FL #	FL5499-R6
Application Type	Revision
Code Version	2023
Application Status	Approved
Comments	
Archived	☐
Product Manufacturer	Elite Aluminum Corporation
Address/Phone/Email	4650 Lyons Technology Parkway Coconut Creek, FL 33073 (954) 949-3200 bpeacock@elitealuminum.com
Authorized Signature	Frank Bennardo P.E. frank@engineeringexpress.com
Technical Representative	Bruce Peacock
Address/Phone/Email	4650 Lyons Technology Parkway Coconut Creek, FL 33073 (954) 949-3200 bpeacock@elitealuminum.com
Quality Assurance Representative	
Address/Phone/Email	
Category	Panel Walls
Subcategory	Storefronts
Compliance Method	Evaluation Report from a Florida Registered Architect Professional Engineer ☐ Evaluation Report - Hardcopy Received
Florida Engineer or Architect Name who developed the Evaluation Report	Frank L. Bennardo, P.E.
Florida License	PE-0046549
Quality Assurance Entity	QAI Laboratories
Quality Assurance Contract Expiration Date	12/31/2025
Validated By	John Henry Kampmann Jr. ☒ Validation Checklist - Hardcopy Received
Certificate of Independence	FL5499_R6_COI_INDEP.pdf
Referenced Standard and Year (of Standard)	Standard AAMA 501 ASTM E1300

ASTM E283
 ASTM E330
 ASTM E331
 TAS 201
 TAS 202
 TAS 203

Equivalence of Product Standards
 Certified By

Florida Licensed Professional Engineer or Architect
[FL5499_R6_Equiv_EQUIV.pdf](#)

Sections from the Code

Product Approval Method

Method 1 Option D

Date Submitted

08/21/2023

Date Validated

09/04/2023

Date Pending FBC Approval

09/08/2023

Date Approved

10/17/2023

Summary of Products

FL #	Model, Number or Name	Description
5499.1	Elite 2000 Storefront	Aluminum Storefront Glazing System L Impact
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: Yes Design Pressure: N/A Other: For use within and outside the HVHZ. Large and Small Missile Impact Resistant.		Installation Instructions FL5499_R6_II_DOC1.pdf Verified By: Frank L. Bennardo, P.E. PE Created by Independent Third Party: Y Evaluation Reports FL5499_R6_AE_EVAL1.pdf Created by Independent Third Party: Y
5499.2	Elite 2000 Storefront	Aluminum Storefront Glazing System N
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: N/A Other: For use within and outside the HVHZ. Non-Impact Resistant.		Installation Instructions FL5499_R6_II_DOC2.pdf Verified By: Frank L. Bennardo, P.E. PE Created by Independent Third Party: Y Evaluation Reports FL5499_R6_AE_EVAL2.pdf Created by Independent Third Party: Y

[Back](#)

[Next](#)

Contact Us :: 2601 Blair Stone Road, Tallahassee FL 32399 Phone: 850-487-1824

The State of Florida is an AA/EEO employer. Copyright 2007-2013 State of Florida. :: Privacy Statement :: Accessibility Sta

Under Florida law, email addresses are public records. If you do not want your e-mail address released in response to a public electronic mail to this entity. Instead, contact the office by phone or by traditional mail. If you have any questions, please contact Section 455.275(1), Florida Statutes, effective October 1, 2012, licensees licensed under Chapter 455, F.S. must provide their address if they have one. The emails provided may be used for official communication with the licensee. However email addresses not wish to supply a personal address, please provide the Department with an email address which can be made available to the public are a licensee under Chapter 455, F.S., please click [here](#).

Product Approval Accepts:





August 29, 2023

Product Approval Administrator
DBPR Codes and Standards
2601 Blair Stone Road
Tallahassee, FL 32399


Regarding: Elite Aluminum Corporation
Elite 2000 Aluminum Storefront Glazing System Large/Small Missile
Impact Resistance- FL #5499.1 – EX # 23-59952
Elite 2000 Aluminum Storefront Glazing System Non-Impact
Resistance – FL #5499.2 – EX # 23-59953

To Whom It May Concern:

Please be advised that the below-signed engineer does not have nor will acquire a financial interest in the company manufacturing or distributing the product(s) for which an evaluation report or validation certification has been prepared, as referenced above. This engineer is not owned, operated, nor controlled by the manufacturer or distributor noted above and does not have any financial interest in any other entity involved in the approval process of the above-noted product(s).

Note: "EX #" where used above is an abbreviation for "Engineering Express (EX) Project Number".

Respectfully,



Digitally signed
by Frank
Bennardo
Date: 2023.08.29
15:13:57 -04'00'

Frank Bennardo, P.E.
ENGINEERING EXPRESS®
#PE0046549 | Cert. Auth. 9885



August 29, 2023

Product Approval Administrator
DBPR Codes and Standards
2601 Blair Stone Road
Tallahassee, FL 32399

Regarding: Elite Aluminum Corporation
Elite 2000 Aluminum Storefront Glazing System Large/Small Missile
Impact Resistance- FL #5499.1 – EX # 23-59952
Elite 2000 Aluminum Storefront Glazing System Non-Impact
Resistance – FL #5499.2 – EX # 23-59953


To Whom It May Concern:

This office has reviewed test report(s) showing structural performance of the above-noted product(s). These test report(s) pertain to testing performed in accordance with the referenced standard(s) in the table shown below. The noted standard(s) are not adopted in the Florida Building Code Eighth Edition (2023); however, for the purpose of determining the performance of the product, the standard(s) are equivalent to the corresponding standard(s), which are adopted in the above-referenced building code.

Code Title	Tests Performed according to:	Current Equivalent Standard
Test Method for Structural Performance of Exterior Windows, Curtain Walls and Doors by Uniform Static Air Pressure Difference	ASTM E330/E330M-02	ASTM E330/E330M-14
Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Difference Across the Specimen	ASTM E283-04	ASTM E283/283M-19
Methods of Test for Exterior Walls	AAMA 501-05	AAMA 501-15

Respectfully,

Frank Bennardo, P.E.
ENGINEERING EXPRESS®
#PE0046549 | Cert. Auth. 9885



Digitally signed
by Frank
Bennardo
Date: 2023.08.29
15:14:47 -04'00'

c:\users\milton\engineering express\production - documents\projects\23-59952 multiple products 2023 fbc update fl 5499\work\2023 fbc\drawings & cad\23-59952a - fl5499.1 - doc.dwg
8/29/2023 11:50 AM MILTON

ELITE 2000 ALUMINUM STOREFRONT GLAZING SYSTEM

LARGE/SMALL MISSILE IMPACT RESISTANCE (LEVEL "D" IMPACT RESISTANCE)
VALID FOR USE INSIDE AND OUTSIDE THE HVHZ (SEE LIMITATIONS HEREIN)
NON-SITE-SPECIFIC STRUCTURAL PERFORMANCE EVALUATION. A DESIGN PROFESSIONAL SHALL BE RESPONSIBLE FOR CERTIFYING THE APPLICATION OF THIS INFORMATION TO ANY SITE-SPECIFIC LOCATION.


GENERAL NOTES

1. THE SYSTEM DESCRIBED HEREIN HAS BEEN DESIGNED AND TESTED IN ACCORDANCE WITH THE FLORIDA BUILDING CODE EIGHTH EDITION (2023), FOR USE WITHIN AND OUTSIDE THE HIGH VELOCITY HURRICANE ZONE (HVHZ),SYSTEM TESTED PER:
- TAS 201-94
- TAS 202-94
- TAS 203-94
- AAMA 501-05
2. WIND LOAD DURATION FACTOR Cd=1.6 HAS BEEN USED FOR WOOD ANCHOR DESIGN.
3. DESIGN PRESSURES NOTED HEREIN ARE BASED ON MAXIMUM TESTED PRESSURES DIVIDED BY 1.5 SAFETY FACTOR.
4. POSITIVE AND NEGATIVE DESIGN PRESSURES CALCULATED FOR USE WITH THIS SYSTEM SHALL BE DETERMINED BY OTHERS ON A JOB-SPECIFIC BASIS IN ACCORDANCE WITH THE GOVERNING CODE. SITE SPECIFIC LOAD WIND LOAD REQUIREMENTS SHALL BE DETERMINED IN ACCORDANCE WITH ASCE 7 AND THE FLORIDA BUILDING CODE EIGHTH EDITION (2023) BY SEPARATE ENGINEERING CERTIFICATION AND SHALL BE LESS THAN OR EQUAL TO THE POSITIVE OR NEGATIVE DESIGN PRESSURE CAPACITY VALUE LISTED HEREIN FOR ANY ASSEMBLY WITHIN THE LIMITATIONS STATED HEREIN.
5. THE SYSTEM DETAILED HEREIN IS GENERIC AND DOES NOT PROVIDE INFORMATION FOR A SPECIFIC SITE. FOR SITE CONDITIONS DIFFERENT FROM THE CONDITIONS DETAILED HEREIN, A LICENSED ENGINEER OR REGISTERED ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE IN CONJUNCTION WITH THIS DOCUMENT.
6. THE ARCHITECT/ENGINEER OF RECORD FOR THE PROJECT SUPERSTRUCTURE WITH WHICH THIS DESIGN IS USED SHALL BE RESPONSIBLE FOR THE INTEGRITY OF ALL SUPPORTING SURFACES TO THIS DESIGN WHICH SHALL BE COORDINATED BY THE PERMITTING CONTRACTOR. WOOD BUCKS (BY OTHERS) SHALL BE ANCHORED PROPERLY TO TRANSFER LOADS TO EXISTING STRUCTURE
7. ANCHOR EMBEDMENT SPECIFIED IS INTO HOST STRUCTURE MINIMUM.
8. ALL EXTRUSIONS SHALL BE 6063-T5 ALUMINUM ALLOY, UNLESS NOTED OTHERWISE.
9. EXTERIOR SEAM OF FRAME CORNERS, INSTALLATION SCREWS, AND GLAZING BEAD ENDS SHALL BE SEALED WITH SILICONE.
10. FASTENERS SHALL BE CADMIUM-PLATED OR OTHERWISE CORROSION-RESISTANT MATERIAL AND SHALL COMPLY WITH "SPECIFICATIONS FOR ALUMINUM STRUCTURES" SECTION J.3.7.2 BY THE ALUMINUM ASSOCIATION IN.C, AND ANY APPLICABLE FEDERAL, STATE AND OR LOCAL CODES.
11. REFER TO FASTENER MANUFACTURER'S PUBLISHED DATA SHEETS AND RECOMMENDATIONS FOR FASTENER INSTALLATION INSTRUCTIONS.
12. ALL BOLTS & WASHERS SHALL BE ZINC COATED STEEL, GALVANIZED STEEL, OR STAINLESS STEEL WITH A MINIMUM TENSILE YIELD STRENGTH OF 60 KSI.

13. THE CONTRACTOR IS RESPONSIBLE TO INSULATE ALL MEMBERS FROM DISSIMILAR MATERIALS TO PREVENT ELECTROLYSIS.
14. SAF GLASS ,LLC. - N.O.A # 13.1105.10 - 0.100" THK.
KURARAY AMERICA INC. - SENTRYGLAS INTERLAYER N.O.A.# 14-0916.11 - 0.090 THK
NOTE: IF THIS N.O.A.# HAS BEEN SUPERSEDED, USE MOST RECENT N.O.A.# VERSION
15. APPROVED FOR LARGE AND SMALL MISSILE IMPACT APPLICATIONS. SEE GLASS TYPES FOR ANY RESTRICTIONS
16. TEST REPORTS: HURRICANE ENGINEERING AND TESTING REPORT # HETI-08-2164B, HETI-08-2164A, HETI-09-2509B AND HETI-09-2509-A. CONSTRUCTION TESTING CORP. REPORT # 00-030
17. THIS SYSTEM MAY BE USED IN CONJUNCTION WITH ELITE DOOR SERIES 3000 OUT SWING ENTRY DOOR
18. CODE REQUIREMENTS FOR SAFEGUARDS MUST BE OBSERVED AND ARE NOT IN THIS CERTIFICATION.
19. WINDOW TO SUBSTRATE WATER PROOFING IS NOT INCLUDED IN THIS DOCUMENT AND MUST BE ADDRESSED ON A SITE SPECIFIC BASIS. NOT BY ELITE ALUMINUM CORP.
20. ENGINEER SEAL AFFIXED HERETO VALIDATE STRUCTURAL DESIGN AS SHOWN ONLY. USE OF THIS SPECIFICATION BY CONTRACTOR, et. al. INDEMNIFIES & SAVES HARMLESS THIS ENGINEER FOR ALL COST & DAMAGES INCLUDING LEGAL FEES & APPELLATE FEES RESULTING FROM MATERIAL FABRICATION, SYSTEM ERECTION, & CONSTRUCTION PRACTICES BEYOND THAT WHICH IS CALLED FOR BY LOCAL, STATE & FEDERAL CODES & FROM DEVIATIONS OF THIS PLAN.
21. EXCEPT AS EXPRESSLY PROVIDED HEREIN, NO ADDITIONAL CERTIFICATIONS OR AFFIRMATIONS ARE INTENDED.
22. PRESSURE VALUES ON THIS APPROVAL ARE (ASD) ALLOWABLE DESIGN PRESSURES.
23. ALTERATIONS ADDITIONS OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE THIS CERTIFICATION.
24. PRODUCT SHALL BE PERMANENTLY LABELED WITH A MINIMUM OF ONE LABEL PER SYSTEM CONTAINING THE FOLLOWING:
ELITE ALUMINUM CORPORATION
4650 LYONS TECHNOLOGY PARKWAY
COCONUT CREEK, FLORIDA 33073
TAS 201/202/203
APPROVED BY FLORIDA BUILDING COMMISSION
FLORIDA PRODUCT APPROVAL NUMBER:
FL#5499.1

FRANK BENNARDO, P.E.
PE# 0046549 CA# 9885

AUGUST 29, 2023



Digitally signed by
Frank Bennardo
Date: 2023.08.29
15:14:12 -04'00'

NOTE REGARDING USE OF THIS DOCUMENT & USE OUTSIDE FLORIDA:

NON-SITE-SPECIFIC STRUCTURAL PERFORMANCE EVALUATION. THIS PRODUCT EVALUATION IS VALID FOR USE IN **FLORIDA ONLY**. USE OF THIS EVALUATION REQUIRES A REVIEW & CERTIFICATION BY A LOCAL DESIGN PROFESSIONAL WHO SHALL BE RESPONSIBLE FOR THE PROPER ADAPTATION OF THIS GENERAL PERFORMANCE EVALUATION TO ANY SITE-SPECIFIC PROJECT. CONTACT THIS OFFICE AT **ENGINEERINGEXPRESS.COM/QUOTE** FOR ASSISTANCE WITH YOUR PROJECT-SPECIFIC NEEDS & FOR ADAPTATION & CERTIFICATION OF THIS DOCUMENT OUTSIDE OF FLORIDA.

SHEET INDEX	
# SHEET	DESCRIPTION
1	COVER SHEET
2	DESIGN DETAILS & ELEVATIONS
3-4	DETAILS
5-7	GLASS LOADING CHARTS
8-10	MULLION LOADING CHARTS
11	ANCHORING SCHEDULE
12	PARTS & PARTS LIST
13	FRAME ASSEMBLY

TERMINOLOGY:

THE FOLLOWING ABBREVIATIONS APPEAR IN THIS APPROVAL: "U.N.O." FOR "UNLESS NOTED OTHERWISE", "FBC" FOR "FLORIDA BUILDING CODE", "CORP." FOR "CORPORATION", "ALUM" FOR "ALUMINUM", "ASD" FOR "ALLOWABLE STRESS DESIGN", "ASTM" FOR "AMERICAN SOCIETY FOR TESTING AND MATERIALS", "CS" FOR "CARBON STEEL", "CONN" FOR "CONNECTION", "EMBED" FOR "EMBEDMENT", "DIST." FOR "DISTANCE", "GA" FOR "GAUGE", "HVHZ" FOR "HIGH-VELOCITY HURRICANE ZONE", "LB" FOR "POUND", "MAX" FOR "MAXIMUM", "N.T.S." FOR "NOT TO SCALE", "PSF" FOR "POUNDS PER SQUARE FOOT (lb/ft²)", "KSI" FOR "KILOPOUNDS PER SQUARE INCH (klb/in²)", "SPECS" FOR "SPECIFICATIONS", "&" FOR "AND", "MAX" FOR "MAXIMUM", "W/" FOR "WITH", "EXIST." FOR "EXISTING", "STRUCT." FOR "STRUCTURE", "SHT" FOR "SHEET", "REF" FOR "REFERENCE", "D.L.O." FOR "DAYLIGHT OPENING". CONTACT ENGINEERING EXPRESS FOR ADDITIONAL ABBREVIATION/TERMINOLOGY CLARIFICATIONS.

VISIT [ECALC.IO/59952](https://ecalculator.com/59952)

FOR SITE-SPECIFIC DEVIATIONS
& MORE INFORMATION ABOUT THIS DOCUMENT
OR SCAN THIS QR CODE

VISIT [ENGINEERINGEXPRESS.COM/STORE](https://engineeringexpress.com/store)
FOR ADDITIONAL PLANS, REPORTS & RESOURCES



FL 5499.1

ENGINEERING
EXPRESS®

POSTAL ADDRESS:
401 W. ATLANTIC AVE R10 BOX 219
DELRAY BEACH, FL 33444
ENGINEERINGEXPRESS.COM

Elite Aluminum Corporation

4650 Lyons Technology Parkway
Coconut Creek, FL 33073

Elite 2000 Storefront Glazing System
Large/Small Missile Impact Resistance
FBC 8TH ED. (2023) | FLORIDA STATEWIDE APPROVAL

REMARKS	DATE	DRWN	CHKD
PREV. SUBMITTAL (20-28074)	01/18/21	JEM	AJP
2023 FBC UPDATE	08/15/23	MRT	RWN

COPYRIGHT ENGINEERING EXPRESS®

23-59952

SCALE: NTS UNLESS NOTED

1 OF 13

FL


FL 5499.1

Elite Aluminum Corporation
4650 Lyons Technology Parkway
Coconut Creek, FL 33073

Elite 2000 Storefront Glazing System
Large/Small Missile Impact Resistance
FBC 8TH ED. (2023) | FLORIDA STATEWIDE APPROVAL

[illegible]**SCALE: NTS UNLESS NOTED**

2 OF 13



FL



Engineering Express

401 W. ATLANTIC AVE R10 BOX 219
DELRAY BEACH, FL 33444
ENGINEERINGEXPRESS.COM

Elite Aluminum Corporation
4650 | Vons Technology Parkway

Coconut Creek, FL 33073

Elite 2000 Storefront Glazing System
Large/Small Missile Impact Resistance

FBC 8TH ED. (2023) | FLORIDA STATEWIDE APPROVAL



REMARKS	DRWN	CHKD	DATE
PREV. SUBMITTAL (20-28074)	JEM	AJP	01/19/21
2023 FBC UPDATE	MRT	RWN	08/15/23
-	-	-	-
-	-	-	-
-	-	-	-

23-59952

SCALE: NTS UNLESS NOTED

3

13




c:\users\milton\engineering express\production - documents\projects\23-59952 multiple products 2023 fbc update fl 5499\work\2023 fbc\drawings & cad\23-59952a - fl5499.1 - doc.dwg
8/29/2023 11:52 AM MILTON


FRANK BENNARDO, P.E.
PE# 0046549 CA# 9885

AUGUST 29, 2023


FL




1
4 JAMB DETAIL
6" = 1'-0"



2
4 JAMB DETAIL
6" = 1'-0"



3
4 JAMB DETAIL
6" = 1'-0"



4
4 VERTICAL INTERMEDIATE DETAIL
6" = 1'-0"

FL 5499.1

ENGINEERING
EXPRESS

POSTAL ADDRESS:
401 W. ATLANTIC AVE R10 BOX 219
DELRAY BEACH, FL 33444
ENGINEERINGEXPRESS.COM

Elite Aluminum Corporation
4650 Lyons Technology Parkway
Coconut Creek, FL 33073

Elite 2000 Storefront Glazing System
Large/Small Missile Impact Resistance
FBC 8TH ED. (2023) | FLORIDA STATEWIDE APPROVAL

REMARKS	DRWN	CHKD	DATE
PREV. SUBMITTAL (20-28074)	JEM	AJP	01/18/21
2023 FBC UPDATE	MRT	RWN	08/15/23

23-59952

SCALE: NTS UNLESS NOTED

4

OF 13

DESIGN PRESSURE CHART (ASD)

GLASS TYPE "A"			
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	24	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		61.9	61.9
48		61.9	61.9
52 3/4		61.9	61.9
60		61.9	61.9
66		61.9	61.9
72		61.9	61.9
78		61.9	61.9
84		61.9	61.9
90		61.9	61.9
96		61.9	61.9
102		61.9	61.9
105 5/16		61.9	61.9
114		61.9	61.9
120		61.9	61.9
126		61.9	61.9
132		61.9	61.9
138		61.9	61.9
144		61.9	61.9
150		61.9	61.9
156		61.9	61.9
162		61.9	61.9

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	30	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		61.9	61.9
48		61.9	61.9
52 3/4		61.9	61.9
60		61.9	61.9
66		61.9	61.9
72		61.9	61.9
78		61.9	61.9
84		61.9	61.9
90		61.9	61.9
96		61.9	61.9
102		61.9	61.9
105 5/16		61.9	61.9
114		61.9	61.9
120		61.9	61.9
126		61.9	61.9
132		61.9	61.9
138		61.9	61.9
144		61.9	61.9
150		61.9	61.9

GLASS TYPE "A"			
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	36	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		61.9	61.9
48		61.9	61.9
52 3/4		61.9	61.9
60		61.9	61.9
66		61.9	61.9
72		61.9	61.9
78		61.9	61.9
84		61.9	61.9
90		61.9	61.9
96		61.9	61.9
102		61.9	61.9
105 5/16		61.9	61.9
114		61.9	61.9
120		61.9	61.9
126		61.9	61.9

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	42	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		61.9	61.9
48		61.9	61.9
52 3/4		61.9	61.9
60		61.9	61.9
66		61.9	61.9
72		61.9	61.9
78		61.9	61.9
84		61.9	61.9
90		61.9	61.9
96		61.9	61.9
102		61.9	61.9
105 5/16		61.9	61.9

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	48	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		61.9	61.9
48		61.9	61.9
52 3/4		61.9	61.9
60		61.9	61.9
66		61.9	61.9
72		61.9	61.9
78		61.9	61.9
84		61.9	61.9
90		61.9	61.9
96		61.9	61.9

GLASS TYPE "A"			
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	52 3/4	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		61.9	61.9
48		61.9	61.9
52 3/4		56	56
60		56	56
66		56	56
72		56	56
78		56	56
84		56	56

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	60	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		61.9	61.9
48		61.9	61.9
52 3/4		56	56
60		49	49
66		49	49
72		49	49

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	66	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		61.9	61.9
48		61.9	61.9
52 3/4		56	56
60		49	49
66		45	45

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	72	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		61.9	61.9
48		61.9	61.9
52 3/4		56	56
60		49	49

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	78	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		61.9	61.9
48		61.9	61.9
52 3/4		56	56

GLASS TYPE "A"			
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	84	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		61.9	61.9
48		61.9	61.9
52 3/4		56	56

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	90	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		61.9	61.9
48		61.9	61.9

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	96	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		61.9	61.9
48		61.9	61.9

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	102	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		60	60

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	105 5/16	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		56	56

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	114	61.9	61.9
30		61.9	61.9
36		55	55

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	120	61.9	61.9
30		59	59
36		49	49

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	126	61.9	61.9
30		53	53
36		45	45

GLASS TYPE "A"			
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	132	60	60
30		48	48


D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	138	55	55
30		44	44

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	144	50	50
30		40	40

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	150	46	46
30		37	37

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	150	43	43

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	162	40	40



GLASS TYPE **A**
GLAZING DETAIL
N.T.S. VERT SECT

NOTE:
GLASS CAPACITY ON THIS SHEET IS BASED
ON ASTM E1300-09 (3 SEC GUST)

FRANK BENNARDO, P.E.
PE# 0046549 CA# 9885

AUGUST 29, 2023

FL

FL 5499.1

ENGINEERING
EXPRESS

POSTAL ADDRESS:
401 W. ATLANTIC AVE R10 BOX 219
DELRAY BEACH, FL 33444
ENGINEERINGEXPRESS.COM

Elite Aluminum Corporation

4650 Lyons Technology Parkway
Coconut Creek, FL 33073

Elite 2000 Storefront Glazing System
Large/Small Missile Impact Resistance
FBC 8TH ED. (2023) | FLORIDA STATEWIDE APPROVAL

REMARKS	DRWN	CHKD	DATE
PREV. SUBMITTAL (20-28074)	JEM	AJP	01/18/21
2023 FBC UPDATE	MRT		08/15/23

COPYRIGHT ENGINEERING EXPRESS®

23-59952

SCALE: NTS UNLESS NOTED

5 OF 13

c:\users\milton\engineering express\production - documents\projects\23-59952 multiple products 2023 fbc update fl 5499\work\2023 fbc\drawings & cad\23-59952a - fl5499.1 - doc.dwg 8/29/2023 11:52 AM MILTON

DESIGN PRESSURE CHART (ASD)

GLASS TYPE "B"			
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	24	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		55.3	55.3
60		55.3	55.3
66		55.3	55.3
72		55.3	55.3
78		55.3	55.3
84		55.3	55.3
90		55.3	55.3
96		55.3	55.3
102		55.3	55.3
105 ⅞		55.3	55.3
114		55.3	55.3
120		55.3	55.3
126		55.3	55.3
132		55.3	55.3
138		55.3	55.3
144		55.3	55.3
150		55.3	55.3
156		55.3	55.3
162		55.3	55.3

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	30	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		55.3	55.3
60		55.3	55.3
66		55.3	55.3
72		55.3	55.3
78		55.3	55.3
84		55.3	55.3
90		55.3	55.3
96		55.3	55.3
102		55.3	55.3
105 ⅞		55.3	55.3
114		55.3	55.3
120		55.3	55.3
126		55.3	55.3
132		55.3	55.3
138		55.3	55.3
144		55.3	55.3
150		55.3	55.3
156		55.3	55.3
162		55.3	55.3

GLASS TYPE "B"			
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	36	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		55.3	55.3
60		55.3	55.3
66		55.3	55.3
72		55.3	55.3
78		55.3	55.3
84		55.3	55.3
90		55.3	55.3
96		55.3	55.3
102		55.3	55.3
105 ⅞		55.3	55.3
114		55.3	55.3
120		55.3	55.3
126		55.3	55.3

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	42	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		55.3	55.3
60		55.3	55.3
66		55.3	55.3
72		55.3	55.3
78		55.3	55.3
84		55.3	55.3
90		55.3	55.3
96		55.3	55.3
102		55.3	55.3
105 ⅞		55.3	55.3
114		55.3	55.3
120		55.3	55.3
126		55.3	55.3

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	48	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		55.3	55.3
60		55.3	55.3
66		55.3	55.3
72		55.3	55.3
78		55.3	55.3
84		55.3	55.3
90		55.3	55.3
96		55.3	55.3
102		55.3	55.3
105 ⅞		55.3	55.3
114		55.3	55.3
120		55.3	55.3
126		55.3	55.3

GLASS TYPE "B"			
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	52 ¾	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		50	50
60		50	50
66		50	50
72		50	50
78		50	50
84		50	50
90		50	50
96		50	50
102		50	50
105 ⅞		50	50
114		50	50
120		50	50
126		50	50

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	60	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		50	50
60		44	44
66		44	44
72		44	44
78		44	44
84		44	44
90		44	44
96		44	44
102		44	44
105 ⅞		44	44
114		44	44
120		44	44
126		44	44

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	66	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		50	50
60		44	44
66		40	40
72		40	40
78		40	40
84		40	40
90		40	40
96		40	40
102		40	40
105 ⅞		40	40
114		40	40
120		40	40
126		40	40

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	72	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		50	50
60		44	44
66		40	40
72		40	40
78		40	40
84		40	40
90		40	40
96		40	40
102		40	40
105 ⅞		40	40
114		40	40
120		40	40
126		40	40

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	78	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		50	50
60		44	44
66		40	40
72		40	40
78		40	40
84		40	40
90		40	40
96		40	40
102		40	40
105 ⅞		40	40
114		40	40
120		40	40
126		40	40

GLASS TYPE "B"			
D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	84	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		50	50
60		50	50
66		50	50
72		50	50
78		50	50
84		50	50
90		50	50
96		50	50
102		50	50
105 ⅞		50	50
114		50	50
120		50	50
126		50	50

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	90	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		50	50
60		50	50
66		50	50
72		50	50
78		50	50
84		50	50
90		50	50
96		50	50
102		50	50
105 ⅞		50	50
114		50	50
120		50	50
126		50	50

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	96	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		50	50
60		44	44
66		44	44
72		44	44
78		44	44
84		44	44
90		44	44
96		44	44
102		44	44
105 ⅞		44	44
114		44	44
120		44	44
126		44	44

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	102	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		50	50
60		44	44
66		40	40
72		40	40
78		40	40
84		40	40
90		40	40
96		40	40
102		40	40
105 ⅞		40	40
114		40	40
120		40	40
126		40	40

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	105 ⅞	55.3	55.3
30		55.3	55.3
36		55.3	55.3
42		55.3	55.3
48		55.3	55.3
52 ¾		50	50
60		44	44
66		40	40
72		40	40
78		40	40
84		40	40
90		40	40
96		40	40
102		40	40
105 ⅞		40	40
114		40	40
120		40	40
126		40	40


D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	114	55.3	55.3
30		55.3	55.3
36		49	49

FL

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	132	85	75
30		85	75
36		74	65
42		64	56

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	90	85	75
30		85	75
36		85	75
42		85	75
48		85	75
52 $\frac{3}{4}$		85	75
60		74	65

D.L.O. WIDTH (in.)	D.L.O. HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	162	72	64
30		58	51



GLASS TYPE 
GLAZING DETAIL
N.T.S. VERT SECT

NOTE:
GLASS CAPACITY ON THIS SHEET IS BASED
ON ASTM E1300-09 (3 SEC GUST)

NOTE:
AN ALUMINUM SKIN PLYWOOD PANEL CONSISTING OF 3/4" PLYWOOD
AND 0.032" THICK 3105H154 ALUMINUM ON INTERIOR AND EXTERIOR
IN LIEU OF GLASS 13 SQ. FT. MAX AREA.

FL 5499.1



EX ENGINEERING EXPRESS®

POSTAL ADDRESS:
401 W. ATLANTIC AVE R10 BOX 219
DELRAY BEACH, FL 33444
ENGINEERINGEXPRESS.COM

Elite Aluminum Corporation

4650 Lyons Technology Parkway
Coconut Creek, FL 33073

Elite 2000 Storefront Glazing System
Large/Small Missile Impact Resistance

FBC 8TH ED. (2023) | FLORIDA STATEWIDE APPROVAL

REMARKS	DRWN	CHKD	DATE
PREV. SUBMITTAL (20-28074)	JEM	AJP	01/18/21
2023 FBC UPDATE	MRT	RWN	08/15/23
-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-

23-59952

SCALE: NTS UNLESS NOTED

FL

FL 5499.1

EX ENGINEERING EXPRESS®

POSTAL ADDRESS:
401 W. ATLANTIC AVE R10 BOX 219
DELRAY BEACH, FL 33444
ENGINEERINGEXPRESS.COM

Elite Aluminum Corporation

0 Lyons Technology Parkway
Coconut Creek, FL 33073

Elite 2000 Storefront Glazing System Large/Small Missile Impact Resistance

Large/Small Missile Impact Resistance
 FBC 8TH ED. (2023) | FLORIDA STATEWIDE APPROVAL

[illegible]

COPYRIGHT ENGINEERING EXPRESS®

23-59952

SCALE: NTS UNLESS NOTED

8

OF
1

21013 VERTICAL MULLION
WITH REINFORCEMENT
TYPE 1

NOMINAL DIMS		PRESSURES	
WIDTH (in.)	HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	54	61.9	61.9
30		61.9	61.9
36		61.9	61.9
42		61.9	61.9
48		61.9	61.9
51		61.9	61.9
54		61.9	61.9
58 3/8		61.9	61.9
66		61.9	61.9
72		61.9	61.9
78		61.9	61.9
84		61.9	61.9
90	61.9	61.9	

72" MAX. WIDTH
± 75 Psf MAX. PRESSURE
ALL HEIGHTS.

21013 HORIZONTAL MULLION

55" MAX. WIDTH
± 56 Psf MAX. PRESSURE
ALL HEIGHTS.

21013 HORIZONTAL MULLION



FL 5499.1

EX ENGINEERING EXPRESS®

POSTAL ADDRESS:
401 W. ATLANTIC AVE R10 BOX 219
DELRAY BEACH, FL 33444
ENGINEERINGEXPRESS.COM

Elite Aluminum Corporation

4650 Lyons Technology Parkway
Coconut Creek, FL 33073

Elite 2000 Storefront Glazing System Large/Small Missile Impact Resistance

FBC 8TH ED. (2023) | FLORIDA STATEWIDE APPROVAL

[illegible]

COPYRIGHT ENGINEERING EXPRESS®

23-59952

SCALE: NTS UNLESS NOTED

9 OF 13

WITH AND WITHOUT HORIZONTALS

MULLION W/ REINFORCEMENT TYPE 2			
NOMINAL DIMS		PRESSURES	
WIDTH (in.)	HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	24	85	75
30		85	75
36		85	75
42		85	75
48		85	75
51		85	75
54		85	75
58 5/8		85	75
66		85	75
72		85	75
78		85	75
84		85	75
90		85	75
96		85	75
99		85	75
102		85	75
108		85	75
109 5/8		85	75
132		85	75
138		85	75
144	85	75	
150	85	75	
156	85	75	
162	85	75	

NOMINAL DIMS		PRESSURES	
WIDTH (in.)	HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	30	85	75
30		85	75
36		85	75
42		85	75
48		85	75
51		85	75
54		85	75
58 5/8		85	75
66		85	75
72		85	75
78		85	75
84		85	75
90		85	75
96		85	75
99		85	75
102		85	75
108		85	75
109 5/8		85	75
132		85	75
138		85	75
144	85	75	
150	85	75	
156	85	75	
162	85	75	

MULLION W/ REINFORCEMENT TYPE 2			
NOMINAL DIMS		PRESSURES	
WIDTH (in.)	HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	36	85	75
30		85	75
36		85	75
42		85	75
48		85	75
51		85	75
54		85	75
58 ⅝		85	75
66		85	75
72		85	75
78		85	75
84		85	75
90		85	75
96		85	75
99		85	75
102		85	75
108		85	75
109 ⅝		85	75
132		85	75
138		85	75
144	85	75	
150	85	75	
156	85	75	
162	85	75	


NOMINAL DIMS		PRESSURES	
WIDTH (in.)	HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	42	85	75
30		85	75
36		85	75
42		85	75
48		85	75
51		85	75
54		85	75
58 ⅝		85	75
66		85	75
72		85	75
78		85	75
84		85	75
90		85	75
96		85	75
99		85	75
102		85	75
108		85	75
109 ⅝		85	75
132		85	75
138		85	75
144	85	75	
150	85	75	

MULLION W/ REINFORCEMENT TYPE 2			
NOMINAL DIMS		PRESSURES	
WIDTH (in.)	HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	48	85	75
30		85	75
36		85	75
42		85	75
48		85	75
51		85	75
54		85	75
58 5/8		85	75
66		85	75
72		85	75
78		85	75
84		85	75
90		85	75
96		85	75
99		85	75
102		85	75
108		85	75
109 5/8	85	75	
132		85	75


NOMINAL DIMS		PRESSURES	
WIDTH (in.)	HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	51	85	75
30		85	75
36		85	75
42		85	75
48		85	75
51		85	75
54		85	75
58 5/8		85	75
66		85	75
72		85	75
78		85	75
84		85	75
90		85	75
96		85	75
99		85	75
102		85	75
108	85	75	
109 5/8	85	75	

MULLION W/ REINFORCEMENT TYPE 2			
NOMINAL DIMS		PRESSURES	
WIDTH (in.)	HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	54	85	75
30		85	75
36		85	75
42		85	75
48		85	75
51		85	75
54		85	75
58 5/8		85	75
66		85	75
72		85	75
78		85	75
84		85	75
90		85	75
96		85	75
99		85	75
102		85	75
108	85	75	
109 5/8	85	75	

NOMINAL DIMS		PRESSURES	
WIDTH (in.)	HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	58 3/8	85	75
30		85	75
36		85	75
42		85	75
48		85	75
51		85	75
54		85	75
58 3/8		85	75
66		85	75
72		85	75
78		85	75
84		85	75
90		85	75
96		85	75
99		85	75
102		85	75
108	85	75	
109 3/8	85	75	




21013 VERTICAL MULLION
WITH REINFORCEMENT
TYPE 2



72" MAX. WIDTH
± 75 Psf MAX. PRESSURE
ALL HEIGHTS.

21013 HORIZONTAL MULLION



55" MAX. WIDTH
± 56 Psf MAX. PRESSURE
ALL HEIGHTS.



21013 HORIZONTAL MULLION

FL

MULLION W/ REINFORCEMENT TYPE 2			
NOMINAL DIMS		PRESSURES	
WIDTH (in.)	HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	102	85	75
30		85	75
36		85	75
42		85	75
48		85	75
51		85	75
54		85	75
58 ⁵ / ₈		85	75

NOMINAL DIMS		PRESSURES	
WIDTH (in.)	HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	108	85	75
30		85	75
36		85	75
42		85	75
48		85	75
51		85	75
54		85	75
58 $\frac{5}{8}$		85	75

NOMINAL DIMS		PRESSURES	
WIDTH (in.)	HEIGHT (in.)	NEGATIVE (Psf)	POSITIVE (Psf)
24	109 $\frac{5}{8}$	85	75
30		85	75
36		85	75
42		85	75
48		85	75
51		85	75
54		85	75
58 $\frac{5}{8}$		85	75



FL 5499.1

**EXENGINEERING
EXPRESS®**

POSTAL ADDRESS:
4401 W. ATLANTIC AVE R10 BOX 219
DELRAY BEACH, FL 33444
ENGINEERINGEXPRESS.COM

Elite Aluminum Corporation

4650 Lyons Technology Parkway
Coconut Creek, FL 33073

Elite 2000 Storefront Glazing System Large/Small Missile Impact Resistance

Large/Small Missile Impact Resistance
FBC 8TH ED. (2023) | FLORIDA STATEWIDE APPROVAL

[illegible]


COPYRIGHT ENGINEERING EXPRESS®

23-59952

SCALE: NTS UNLESS NOTED

10

FL



JAMB ANCHOR LAYOUT (INTO WOOD)



TYPE 'A'

CONCRETE	<u>DIRECTLY INTO CONCRETE OR GROUT FILLED BLOCK (3000 PSI. MIN. / f'm=2000 Psi MIN.)</u> <u>5/16" DIA. ULTRACON BY 'DEWALT' (Fu=177 KSI, Fy=155 KSI)</u> <u>1-1/2" MIN. EMBEDMENT</u>
TYPE 'B'	
WOOD	<u>INTO 2BY WOOD BUCKS OR WOOD STRUCTURES (SYP#2</u> <u>G=0.55 MIN. 1 1/2" MIN. THICKNESS)</u> <u>5/16" DIA. ULTRACON BY 'DEWALT' (Fu=177 KSI, Fy=155 KSI)</u> <u>1-1/2" MIN. PENETRATION</u>
TYPE 'C'	
METAL	<u>INTO METAL STRUCTURES (3 PINCHES PASS THE THREAD</u> <u>PLANE MIN.) STEEL: 1/8" THK MIN. (Fy=36 KSI MIN)</u> <u>ALUMINUM: 1/8" THK MIN. (6063-T5 MIN)</u> <u>5/16-24 DIA. DRIL-FLEX BY 'DEWALT' (GRADE 5 MIN)</u> <u>(STEEL IN CONTACT WITH ALUMINUM TO BE PLATED OR</u> <u>PAINTED)</u>
<u>TYPICAL EDGE DISTANCE</u> <u>INTO CONCRETE/HOLLOW BLOCK/GROUT FILLED BLOCK=</u> <u>2-1/2" MIN.</u> <u>INTO WOOD STRUCTURE = 1" MIN.</u> <u>INTO METAL STRUCTURE = 3/4" MIN.</u>	

**ENGINEERING
EXPRESS®**

POSTAL ADDRESS:

401 W. ATLANTIC AVE R10 BOX 219
DELRAY BEACH, FL 33444
ENGINEERINGEXPRESS.COM

Coconut Creek, FL 33073

Elite 2000 Storefront Glazing System
Large/Small Missile Impact Resistance
FBC 8TH ED. (2023) | FLORIDA STATEWIDE AP

[illegible]**SCALE: NTS UNLESS NOTED**




2.6252

4.0000


0.0780
TYP

ENGINEER
EXPRESS


① VERTICAL MULLION




2 VERTICAL MULLION
INSERT (REINF.)




3 VERTICAL MULLION REINFORCEMENT




4 PERIMETER EXTRUSION




5 CONNECTION BRACKET



6 GLAZING CLIP
(ROUNDED)



7 GLAZING CLIP
(ROUNDED)



8 SNAP TRIM (ROUNDED)

PARTS LIST			
	PART	MATERIAL	PART No.
1	VERTICAL MULLION	ALU 6063-T5	21013
2	VERTICAL MULLION INSERT	ALU 6063-T6	API-2510
3	VERTICAL MULLION REINFORCEMENT	ALU 6063-T5	22056
4	HEAD/ SILL/ JAMB / HORIZ. INTERMEDIATE	ALU 6063-T5	21002
5	CONNECTION BRACKET	ALU 6063-T6	22001
6	GLAZING STOP	ALU 6063-T5	22119
7	GLAZING STOP	ALU 6063-T5	22107
8	SNAP TRIM	ALU 6063-T5	-

PARTS LIST			
	PART	MATERIAL	PART No.
1	VERTICAL MULLION	ALU 6063-T5	21013
2	VERTICAL MULLION INSERT	ALU 6063-T6	API-2510
3	VERTICAL MULLION REINFORCEMENT	ALU 6063-T5	22056
4	HEAD/ SILL/ JAMB / HORIZ. INTERMEDIATE	ALU 6063-T5	21002
5	CONNECTION BRACKET	ALU 6063-T6	22001
6	GLAZING STOP	ALU 6063-T5	22119
7	GLAZING STOP	ALU 6063-T5	22107
8	SNAP TRIM	ALU 6063-T5	-

FL 5499.1



**ENGINEERING
EXPRESS®**

POSTAL ADDRESS:
401 W. ATLANTIC AVE R10 BOX 219
DELRAY BEACH, FL 33444
ENGINEERINGEXPRESS.COM

Elite Aluminum Corporation
4650 Lyons Technology Parkway

4650 Lyons Technology Parkway
Coconut Creek, FL 33073

Elite 2000 Storefront Glazing System
Large/Small Missile Impact Resistance

FBC 8TH ED. (2023) | FLORIDA STATEWIDE APPROVAL

[illegible]

23-59952

SCALE: NTS UNLESS NOTED

12 13

FL

FL 5499.1

EXENGINEERING[®]EXPRESS[®]

401 W. ATLANTIC AVE R10 BOX 219
DELRAY BEACH, FL 33444
ENGINEERINGEXPRESS.COM

Elite Aluminum Corporation
4650 | Vons Technology Parkway

4650 Lyons Technology Parkway
Coconut Creek, FL 33073

Elite 2000 Storefront Glazing System
Large/Small Missile Impact Resistance

FBC 8TH ED. (2023) | FLORIDA STATEWIDE APPROVAL


REMARKS	DRWN	CHKD	JEM	AJP	RWN	DATE
PREV. SUBMITTAL (20-28074)						01/18/21
2023 FBC UPDATE	MRT					08/15/23
-			-	-	-	-
-			-	-	-	-
-			-	-	-	-

COPYRIGHT ENGINEERING EXPRESS®

23-59952

SCALE: NTS UNLESS NOTED

13




FRAME ASSEMBLY DETAIL

NOTE:
SEAL ALL CORNERS WITH
DOWSIL 795 SILICONE OR
C.R. LAURENCE SJ88
NARROW JOINT SEALER.

SEE ELEVATION AND
ANCHOR SCHEDULE
FOR ANCHOR
REQUIREMENTS.

EXISTING HOST
STRUCTURE BY
OTHERS, TYP.



(2) #12 SMS PER
CONNECTION
BRACKET TO
PERIMETER
EXTRUSION

CONNECTION BRACKET DETAIL

N.T.S.

SECTION

ENGINEERING EXPRESS® (EX) PRODUCT EVALUATION REPORT

August 29, 2023

Application Number: FL 5499.1
EX Project Number: 23-59952

Product Manufacturer: Elite Aluminum Corporation
Manufacturer Address: 4650 Lyons Technology Parkway
Coconut Creek, FL 33073

Product Name & Description: Elite 2000 Aluminum Storefront Glazing System
Large/Small Missile Impact Resistance

Scope of Evaluation:

This Product Evaluation Report is being issued in accordance with the requirements of the Florida Department of Business and Professional Regulation (Florida Building Commission) Rule Chapter 61G20-3.005, F.A.C., for statewide acceptance per Method 1 (d). The product noted above has been tested and/or evaluated as summarized herein to show compliance with standard ASCE 7-22 (ASD) and the Florida Building Code Eighth Edition (2023) and is, for the purpose intended, at least equivalent to that required by the Standard and Code. Re-evaluation of this product shall be required following pertinent Florida Building Code or ASCE Standard modifications or revisions.

Substantiating Data:

- **PRODUCT EVALUATION DOCUMENTS**

EX Performance Evaluation document # 23-59952 titled "Elite 2000 Aluminum Storefront Glazing System Large/Small Missile Impact Resistance", prepared by Engineering Express, Inc., signed & sealed by Frank Bennardo, P.E. is an integral part of this Evaluation Report, pages 1 through 13.

- **TEST REPORTS**

The product has been tested per the following:

Uniform static structural performance has been tested in accordance with TAS 202 test standards per test report(s) #00-030 by Construction Testing Corporation (CTC). Signed by Yamil G. Kuri, P.E.

Uniform static structural performance, water and air infiltration performance have been tested in accordance with ASTM E330-02, ASTM E331-00 and ASTM E283-04, respectively. Large missile impact resistance and cyclic loading performance have been tested in accordance with TAS 201 & 203 test standards per test report(s) #00-030 by Construction Testing Corporation (CTC) Signed by Yamil G. Kuri, P.E. & test report(s) HETI-08-2164A/B, HETI-09-2509A/B by Hurricane Engineering and Testing Inc. Signed by Candido F. Font, P.E.

Elite Aluminum Corporation - Elite 2000 Aluminum Storefront Glazing System
Large/Small Missile Impact Resistance

- **STRUCTURAL ENGINEERING CALCULATIONS**

Structural engineering calculations have been prepared which evaluate the product based on comparative and/or rational analysis to qualify the following design criteria:

1. Maximum Allowable Spans
2. Minimum Allowable Pressures
3. Anchor Spacing
4. Glass Capacity

The following is approved for use in the HVHZ as specified in its corresponding NOA:

- Polycarbonate Interlayer by SAF-GLAS, LLC. (NOA #13-1105.10) or a superseded version approved by Miami-Dade BCCO.

Impact Resistance:

Large/Small Missile Impact Resistance has been demonstrated as evidenced in previously listed test reports, and is accounted for in the engineering design of this product.

Wind Load Resistance:

This product has been designed to resist wind loads as indicated on its respective Performance Evaluation document (i.e. engineering document).

Installation:

The product listed above shall be installed in strict compliance with the Performance Evaluation document (i.e. engineering document), along with all components noted therein.

The product components shall be of the material specified in the Performance Evaluation document (i.e. engineering document).

Limitations & Conditions of Use:


Use of each product shall be in strict accordance with its respective Performance Evaluation document (i.e. engineering document) as noted herein.

All supporting host structures shall be designed to resist all superimposed loads and shall be of a material listed in each product's respective anchor schedule. Host structure conditions which are not accounted for in each product's respective anchor schedule shall be designed for on a site-specific basis by a registered professional engineer.

All components which are permanently installed shall be protected against corrosion, contamination, and other such damage at all times. Any alteration to the respective Performance Evaluation document will invalidate it. This product has been designed for use inside and outside of the High Velocity Hurricane Zone (HVHZ & NON-HVHZ).

Respectfully,

Frank Bennardo, P.E.
ENGINEERING EXPRESS®
#PE0046549 | Cert. Auth. 9885



Digitally signed
by Frank
Bennardo
Date: 2023.08.29
15:15:07 -04'00'